

R. A. SANDERS Building & Property Maintenance.

12 Cherry Tree Rise,
Drinkstone,
Bury St Edmunds,
Suffolk. IP30 9UN

25th November 2024
email;ryansanders78@outlook.com
Mob;07840343571

Quote for proposed muntjac fencing at: Rattlesden Road
Allotments, Drinkstone Green.

To cut back and clear existing vegetation along and behind the
existing fence line and dispose of green waste.

To remove existing fence posts and line wires (Retain existing
rabbit netting in situ.)

To supply and erect approx 145 metres of 1.5m high tensile steel
stock netting with high tensile steel top line wire. With 2.1m x
100mm diameter round, treated softwood posts at 4 metre spacing.
Posts driven in minimum 550mm.

To supply and erect 2.4m x 150mm straining posts (175mm posts not
marketed.) to end runs, gates and changes in direction, with 50mm
diameter round post supports for straining posts.

To supply and erect 2 x timber pedestrian field gates with
galvanised field gate furniture, 150mm x 150mm timber gate posts
and rabbit netting attached. (Timber field gates are only
sold/available at 1.27m total height.)

***** TOTAL QUOTE MATERIALS & LABOUR £4700.00 *****

R. A. SANDERS Building & Property Maintenance.

12 Cherry Tree Rise,
Drinkstone,
Bury St Edmunds,
Suffolk. IP30 9UN

25th November 2024
email;ryansanders78@outlook.com
Mob;07840343571

Quote for proposed muntjac fencing at: Gedding Road Allotments,
Drinkstone Green.

To cut back existing vegetation and lower ground level beside the
field gate on Gedding Road and dispose of green waste.

To supply and erect approx 115 metres of 1.2m high tensile steel
stock netting with high tensile steel top line wire. With 1.8m x
100mm diameter round, treated softwood posts at 4 metre spacing.
Posts driven in minimum 550mm.

To supply and erect 2.1m x 150mm straining posts (175mm posts not
marketed.) to end runs, gates and changes of direction, with 50mm
diameter round post supports for straining posts.

To replace both field gate posts with 200mm x 200mm treated
timber gate posts, with 4 way weather tops and concrete in
position.

To supply and erect a new pedestrian timber field gate on Chapel
Lane frontage with galvanised field gate furniture, 150mm x 150mm
timber gate posts. Gate to be 1.2m high with rabbit netting
attached.

***** TOTAL QUOTE MATERIALS & LABOUR £4450.00 *****